



Commissioning of the Advanced Rare Isotope Separator ARIS at FRIB

Mauricio Portillo

Facility for Rare Isotope Beams, Michigan State University, East Lansing, MI 48824 USA

EMIS 2022, Oct 3-7
Science Culture Center, IBS at Daejeon, Korea

MICHIGAN STATE
UNIVERSITY



U.S. DEPARTMENT OF
ENERGY

Office of
Science

This material is based upon work supported by the U.S. Department of Energy Office of Science under Cooperative Agreement DE-SC0000661, the State of Michigan and Michigan State University. Michigan State University operates FRIB as a DOE Office of Science National User Facility in support of the mission of the Office of Nuclear Physics.

Outline


- Introduction/Layout
- Description of ARIS in-flight separator
 - Comparisons to previous facility
 - Optics properties
- Preparation of newly designed and built magnets
- Phased approach to power ramp up
 - Targets
 - Beam dumps
- Commissioning and first experiments



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University


FRIB Layout

- Below ground linac and separator transport RIB's to ground level
 - Conceptual design started ~2010
 - Constructions started ~2014



FRIB Primary Beams for First Experiments

- Many beams have already been developed at low power in linac
- Commissioning and early 2022 experiments
 - Started with 1 kW beams. Next, 3 kW
- Working towards 10 kW operations in 2023 for most beams.



Used or ready for experiments

Beam	Early 2022 comm. & exper.	End Station
^{16}O		
^{18}O		
^{36}Ar		
^{48}Ca	April	FDSi
$^{70}\text{Zn}^*$	July-Aug.	S800
^{82}Se	June	FDSi
^{78}Kr		
^{86}Kr		
^{124}Xe		
^{238}U		

* ^{70}Zn not planned initially


O. Tarasov



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University


M. Portillo, EMIS 2022-Daejeon, Slide 4

FRIB Layout: Linac



- Linac, target and dump
 - 30 ft. underground
 - early operations started in 2018
- Demonstrated 200 MeV/u operations
 - Early 2021
- Demonstrated multi-q state operations
 - Summer of 2021
 - ^{124}Xe 212 MeV/u (49+, 50+, 51+)

FRIB Layout: Separator and Experiment Areas




- **ARIS separator**
 - transports RIBs to ground level
 - early operations in 2022
- **First experiments at FDSi and S800**
(FDSi is a new decay station)
- **Preparing for re-commissioning of stopping areas**
 - Low-E and Reaccelerator stations have been using imported long-lived sources during transition

Understanding Evolution to ARIS from Past

■ Past NSCL facility


- consisted of one-stage separation
- static target for highest power operation (~2 kW max)
- limited intensities due to
 - » acceptance limits of cyclotrons & lifetime of stripping foils

NSCL Layout of accelerators and separator system



NSCL method of dumping primary beams

- Dumping beam into or close to SC magnets
 - Not practical for operation and lifetime of equipment
 - » Power losses to cryo system sets limitations
 - » Designing for 400 kW operations very challenging




ARIS Fragment Separator

■ Multi-stage separation

- Reduces impurity rates for tracking at later stages
- First stage applies $\sim 3\times$ momentum compression
 - » better matching to existing beam lines


- Applies vertical separation
- Horizontal stages can operate as one or two achromatic foci
 - » Single stage mode offers higher resolving power but less acceptance

Hausmann, NIMB 317 (2013) 349.




ARIS design does not allow direct primary beam losses on dipole parts

- First dipole will experience substantial stray beam losses
 - Apertures wide enough to minimize them




SCD1(type FSD1) Thermal Armor Design

- Stray losses at first dipole (after target) are still considerable
 - Worst case scenarios were accounted for in thermal armor (shield) design
 - Maximum allowed power removal shown
 - Cooling lines on dipole pole tips also exist (not shown)



All Preseparator Magnets Designed and Built during FRIB Project

- Several types of magnets used to account for high power/radiation environment



- FSQ1 uses room-temp. coils – spare acquired in early 2021
- FSQ5 – planning to build one more (spare and future optics upgrade)
- FST1 – CIQT (Cold Iron Quad Triplets) with Q7,Q8 quad. types – S800 triplets for spare
- FST2 – CIQT with Q9,Q10 types (smaller bore) – 2 smaller doublets used for spare



Preseparator Target Hall WIQ Types

- Target Hall magnets all have Warm Iron yokes

- Minimizes heat transfer to cryogenics
- All but first quad have SC coils with nested sext. & octupoles
- Yokes closest to target
 - » water cooled and
 - » thermal armor installed in bore region

Type	FSQ1(RT)	FSQ2	FSQ5
L_{eff} (m)	0.6	0.75	0.7
Full aperture (m)	0.208	0.22	0.4
Quad. g_M (T/m)	11.3	13.3	10
Sext. g_M (T/m ²)		4.5	6.1
Oct. g_M (T/m ³)		12.7	13.5

- FSQ1 (WIQ1) during testing/field mapping
- Maps in good agreement with model






March 2019

Mapped All SC Warm Iron Quadrupoles

- FSQ2 & 5 designed, built, and mapped in-house
- Completed between 2018 and 2020


Mapper: Hall sensor every 5°
about a ring

Designed for remote
assembly/disassembly in Target Hall



Laser tracker system
for alignment data

FSQ2 type multipole




Preparation of Target Hall Magnets

- Installation started 2019

- Commissioned for use in Dec 2021.

Wei, Mod. Phys. Let. A (2022) 2230006.
First isotope separation and identification.



Preseparator Optics

Comparison to A1900 up to Wedge

■ Some trade-offs in going to ARIS

- » Less angular acceptance
- » higher Brho
- » higher $\Delta p/p$ -accept
- » gain in resolving power at dump

	A1900	ARIS
Brho max. [T-m]	6	8
$\Delta p/p$ -accept. [%]	5.5	10

Angular acceptance

Solid angle [msr]	7.5	6.4
dispersive [mrad]	± 60	± 40
non-disp. [mrad]	± 40	± 40

Properties at dump

Dispersion [cm/%]	0.91	0.92
Resolving power	NA*	756



Properties at wedge

Mx	2.35	-1.39
Dispersion [cm/%]	-5.91	-2.56
Resolving power	2515	1842

1st order properties


Resolving power = Dispersion/ X_0 *Mx, x_0 is beam spot size at target (assumed 1 mm)

* Dump region does not have a focus along dispersive direction.



Mapped all Cold Iron Quadrupole Triplets

- Final (fourth) CIQT mapped in July 2022
 - Not used during commissioning
 - » Just installed Sept-Oct for upcoming beam time starting mid-November



	CIQT1-3		CIQT4	
Type	FSQ7	FSQ8	FSQ9	FSQ10
L_{eff} (m)	0.65	0.8	0.65	0.8
Full aperture (m)	0.4	0.4	0.3	0.3
Quad. g_M (T/m)	9.3	9.9	8.5	9.8
Sext. g_M (T/m ²)	6.05	6.05	7.8	2.9
Oct. g_M (T/m ³)	13.5	13.5	22.5	13.7

Preseparator Optics

Comparison to A1900 up to Achromatic Focus


- ARIS normal mode design
 - Imposes compression factor $\kappa \approx 3$
 - Modes with $\kappa=1$ have less acceptance

Wedge to FP	A1900	ARIS
Dispersion [cm/%]	6.3	8.4
<i>Properties at FP</i>		
Mx	2.4	5.8
My	3.4	-1.5
$\kappa=1/(\delta \delta)_{tot}$	1	3.05
Total Length [m]	35.8	46.5


Mx is magnification in dispersive plane.

$$\kappa = \frac{1}{(\delta|\delta)_{tot}} = -\frac{(x|\delta)_2}{(x|x)_2(x|\delta)_1}$$

Bandura, NIMA 645 (2011) 182.





ARIS total, ray plot, 1st order



Common Magnet Types Show Agreement in Mapping Results

- Was mapping all of them worth it?
 - Yes.
 - » Some integrated strengths varied from average by $\sim 1\%$
 - » Difference from model as much as $\sim 2\%$ in some regions
 - Noticeable difference in optics





Phased Approach for Targets

- Three types of target modules to be used in power ramp up phases

- Commissioned with static multi-target

- Allows visible spectrum cameras
- 1 kW \Rightarrow 0.37 kW on 8.9 mm Be


- 5 positions used on each Be
- 5e12 Gy max dose allowed



Next Phases Utilize a Rotating Target Module

- Single-slice installed Sep 2022
 - 50 kW max capability (depends on beam)
 - 1.9 g/cm³ graphite
- Multi-slice operation projected for operation by 2025

- 1) entrance to multi-slice
- 2) Cu heat exchanger




Pellemoine, NIMB 317 (2013) 369.




Various Beam Dump Systems

- Started with static beam dumps that are simpler to operate
 - Maximum power depends on beam

Commissioned with
20° static beam dump
Operated up to 1 kW





Next phase
6° static beam dump
>10 kW max allowed



Primary beam does
not stop in water

Beam Markings on Dump Entrance Plane in Agreement with Model



Rotating Beam Dump Under Testing

- Designed for 400 kW operation
 - Maximum absorbed power ~325 kW
 - Most primary beam & other products stop in water
 - Start with 1 mm thick wall
 - » 400 kW for lighter beam operations
 - » ~40 kW for uranium
 - Working towards ~0.5 mm wall



Hausmann, NIMB 317 (2013) 349.

Preseparator Wedge Module Upgrades

- Upgrades to wedge systems are planned
 - Simplified lower power module used for first beams
 - » Hands-on maintenance allowed
 - Higher power modules ahead for remote handling
- 3 wedges per ladder at 3 stations

250 mm wide Al wedge (5083 Alloy)



ARIS Beam Activities

- **Mainly commissioning developments, but also some experiments**
 - Gradually (safely) ramping up beam power
 - » Note that machine & personnel protection systems also being commissioned

- **2021**
 - Dec. – First rare isotopes separated and identified Dec. 2021
 - » Magnet polarity and misalignment studies; calibration of dipoles

- **2022**
 - Jan. – First primary beam transport through all separator stages
 - » Magnet misalignment studies
 - Mar. – Power ramp up studies through Beam Delivery System (BDS)
 - April – Commissioning and experiments at FDSi (^{48}Ca , ^{82}Se)
 - July-Aug. – Commissioning and experiments at S800 (^{70}Zn)





Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

M. Portillo, EMIS 2022-Daejeon, Slide 27



Optics Correction Methods

- Phase space measured
 - Preseparator focal plane
 - » No optics corrections



- After optics corrections
 - » Method described elsewhere in this conference

Kei Fukushima-Poster
PS-6-3



Summary

- FRIB has completed all ARIS separator magnets
- ARIS commissioning was completed in early 2022
- Optics studies confirm expected optics and correction methods
- A phased power ramp up approach started; up to 1 kW
- Improvements from lessons learned are on-going



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

Acknowledgements

- For invitation and attention

- Collaborators

Yoonhyuck Choi, Xiaoji Du, Ting Xu, Hai Ngun

Kei Fukushima, Marc Hausmann, Elaine Kwan, Peter Ostroumov, Ryan Ringle,
Mallory Smith, Mathias Steiner, Oleg Tarasov, Antonio Villari, Tong Zhang

This material is based upon work supported by the U.S. Department of Energy, Office of Science, Office of Nuclear Physics and used resources of the Facility for Rare Isotope Beams (FRIB), which is a DOE Office of Science User Facility, operated by Michigan State University, under Award Number DE-SC0000661



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University