

RAON Beam Plan for Early Phase Experiment

Taeksu Shin
Institute for Basic Science

Nov 26, 2022

**Focused Workshop on Rare Isotope Physics
At Yeosu**

Rare Isotope Science Project(RISP)

- **Goal:** To build a heavy ion accelerator complex RAON, for rare isotope science research in Korea.

* **RAON (라온)- Rare isotope Accelerator complex for ON-line experiments**

- **Budget:** **KRW 1,518 billion (US\$ 1.32 billion, 1\$=1,146krw)**

- accelerators and experimental apparatus : 522.8 billion won


- civil engineering & conventional facilities : 996 billion won (incl. site 357 billion won)

- **Period:** **2011.12 ~ 2022.12 (1st Phase)**

2023.1 ~ 2027.12 (2nd Phase: Just constructing SCL2)

System Installation Project

Development, installation, and commissioning of the accelerator systems that provides high-energy (200MeV/u) and high-power (400kW) heavy-ion beam



- ◆ **Providing high intensity RI beams by ISOL and IF**

- ISOL: direct fission of ^{238}U by 70 MeV proton
 - IF: 200 MeV/u ^{238}U (intensity: 8.3 μA)

Facility Construction Project

Construction of research and support facility to ensure the stable operation of the heavy-ion accelerator, experiment systems, and to establish a comfortable research environment

※ Accelerator and experiment buildings, support facility, administrative buildings, and guest house, etc.



- ◆ **Providing high quality neutron-rich beams**

e.g., ^{132}Sn with up to 250 MeV/u,
 up to 10⁹ particles per second

- ◆ **Providing More exotic RI beam production by combination of ISOL and IF(ISOLIF)**

Bird's-eye-view of RAON



Science Goals of RAON



RAON
Accelerator complex
ISOL + In-Flight Fragmentation

Origin of Matter


- Nuclear Astrophysics
- Nuclear Matter
- Super Heavy Element Search
- High-precision Mass Measurement

Properties of Exotic Nuclei


- Nuclear Structure
- Electric Dipole Moment and Symmetry
- Nuclear Theory
- Hyperfine Structure Study

Applied Science

- Bio-Medical Science
- Material Science
- Neutron Science




SCL3 and SCL2




ISOL -> LEBT

SCL3




SCL2






Injector System

- Two ECR IS's
 - 14.5 GHz ECR ion source
 - 28 GHz superconducting ECR ion source
- LEBT ($E = 10 \text{ keV/u}$)
 - 10 keV/u, Dual bending magnet
 - Chopper & Electrostatic quads, Instrumentation
- RFQ ($E = 500 \text{ keV/u}$)
 - 81.25 MHz, Transmission efficiency $\sim 98\%$
 - CW RF power 94 kW (SSPA: 150 kW)
- MEBT ($E = 500 \text{ keV/u}$)
 - Four RF bunchers (SSPA: 20 kW, 15kW, 2 X 4 kW)
 - Simple quadrupole magnets, Instrumentation




Ar⁸⁺ 10 μ A @ Beam Viewer('21)





Beam Commissioning of Injector

- Started in Aug 2021
- Ar^{8+,9+} (1Hz, 10μs)
- ECR(14.5 GHz) → LEPT → RFQ → MEPT





Injector beam commissioning

Parameter	Value
[Beam Properties]	
Frequency	81.25 MHz
Particle	H ¹⁺ to ²³⁸ U ³³⁺
Input energy	10 keV/u
Input current	0.4 mA
Input emittance	0.012 cm·mrad
Output energy	0.507 MeV/u
Output emittance	0.0125 cm·mrad
Transmission	~98% (simulation)
Duty factor	100%



- Beams
 - Ar⁹⁺ (~30 μA) & Ar⁸⁺ (~47 μA): 100 μs long pulsed beam
 - Repetition rate: 1 Hz
- EPICS basis control system
- RFQ transmission
 - Measured by ACCTs in LEBT & MEBT (Error bar: 3σ)
 - Ar⁹⁺ (91.9% w/ σ=1.9%) & Ar⁸⁺ (95.4% w/ σ=1.3%)
- Energy
 - 507 keV/u by ToF using the two BPMs in MEBT




SCL3 Installation

SCL3 Installation finished in 2021



- Cryomodule & Warm section are assembled in the clean booth.
- Total particle counts < 30 counts (size=0.5 μ m above/10 mins)



SCL3 LINAC

Cryogenic System

- SCL3 cryoplant (4.2 kW @ 4.5 K)



Compressors and Oil Removal System (WCS)

Cold Box(CB)

- SCL2 cryoplant (13.5 kW @ 4.5 K)



Compressors and Oil Removal System (WCS)



Cold Box (CB)


(Left warm side, right – cold side)

SCL3 Cryoplant was commissioned in Aug 2022

Cryogenic System


■ Cryogenic Distribution System

- All QWR VBx are installed and assembled (VBx-VBx, VBx-CM).
- All HWR VBx are installed and assembled @ SCL3.
- Cryogenic transfer Lines are installed
- SSR1 VBx : 23 ea, SSR2 VBx : installed



The First Cool-Down of SCL3

Cooling down cryogenic distribution system, thermal shields of all cryomodules with SCL3 cryoplant.




The first cool-down started on Sep. 7, 2022 (15:30)

RF Control Test of SCL3


RF Control Test(Amplitude/Phase feedback with Tuner control)

RF Amplitude, Phase Control




- Target RF amplitude error < 1%, phase error < 1deg
- Tuner operation threshold : +/- 5deg
- Control bandwidth: 90~160 Hz

The First Success of SCL3 Beam Commissioning Exp (Oct. 7, 2022)



Result of the 1st SCL3 Beam Commissioning Exp




Ar⁹⁺ beams accelerated by QWR #1~#5 on the 7th of Oct, 2022 at 15:03




RF set-point for QWR cavities

- RF set-point of 5 QWR cavities by phase scan method:
 - Beam phase was measured by BPM (phase difference between 2 BPMs)
 - QWR2: problems in the 2nd BPM data $\Rightarrow$ using single BPM
- QWR2: multipacting at RF amplitude set value $\Rightarrow$ Increase RF amp by 12%
 $\Rightarrow$ Adjust synchronous phase
- QWR3/QWR4: RF control is maintained for only 20 or 30 minutes in phase scan.




[Phase scan of QWR2]



[Phase scan of QWR5]

Beam Energy in 5 QWRs

- ❑ The energy at the exit of each QWR was determined in phase scan process:
 - Energies are slightly lower than TRACK estimation
 - Energy after QWR5 = 697 keV/u (TRACK: 712 keV/u)
 - In order to get energy > 700 keV/u, we increase RF amplitude of QWR5.



SCL3 Beam Commissioning Plan

SCL3 Beam Commissioning Master Schedule

● 작성일 : 2022. 09.13


● 작성자 : 중이온가속기연구소

구분 (System)	주요업무 (Activity)	시작 (Start)	완료 (Finish)	기간 (day)	2022년												2023년																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
					2월			3월			4월			5월			6월			7월			8월			9월			10월			11월			12월			1월			2월			3월																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
					7	14	21	28	7	14	21	28	4	11	18	25	2	9	16	23	30	6	13	20	27	4	11	18	25	1	8	15	22	29	5	12	19	26	3	10	17	24	31	7	14	21	28	5	12	19	26	2	9	16	23	30	6	13	20	27	6	13	20	27																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Cryogenics System	★ SCL3 Cryoplant																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			


- Finished cooling-down of SCL3 on Oct. 26, 2022.
- Commissioning of SCL3 to be finished until March 2023
- From March 2023, beams on KoBRA spectrometer

Uniqueness of RAON: RIB Production

	KoBRA	ISOL	IF Separator
RIB production & acceleration mode	ECR (SIB) → SCL3 → KoBRA production target	Cyclotron (p) → TIS (RIB) → SCL3	ECR (SIB) or ISOL (RIB) → SCL3 → SCL2 → IF (RIB)
Production Mechanism	Direct reactions & Multi Nucleon Transfer	p induced U fission	Projectile Fragmentation (U fission)
RIB Energy	< a few tens of MeV/u	> a few of keV/u	< a hundreds of MeV/u



Expected RIs from RAON



● RAON is expected to access more neutron-rich regions of the nuclear chart


KoBRA Spectrometer

Korea Broad acceptance Recoil spectrometer and Apparatus





Goal: Construction of **multi-purpose experimental instrument** using stable or RI beams for studies of the nuclear structure and nuclear astrophysics, in the energy range of about 1 – 30 MeV/u

- ❖ RI beam productions at a few MeV/u and at about 20 – 40 MeV/u using a stable beams from ECR ion source
- ❖ Recoil mass separator at less than few MeV/u for direct measurements of radiative-capture cross, using a RI beams from ISOL facility





KoBRA Spectrometer

KoBRA machine commissioning completed on 2021.10




Alpha source (^{241}Am)



KoBRA Beam Experiment : Plan

- Primary beam : 25 MeV/u ^{40}Ar with intensity of 100 pnA ($\sigma_{x,y}=1$ mm, $\sigma_{\theta,\phi}=2$ mrad)
- Production target : 0.1 mm-thick graphite (or Be with thickness 0.1-0.2 mm)
- Swing angle on production target : -30 mrad (or adjustable 0-200 mrad)
- Completely Rejected: $^{40}\text{Ar}^{18+}$, $^{40}\text{Ar}^{17+}$, $^{40}\text{Ar}^{16+}$ ($^{40}\text{Ar}^{15+}$ can be transport to F2)
- Detectors:
 - F1 chamber : Large area PPAC (resolution of 0.4 mm in σ)
 - F2 chamber : PPAC and Plastic scintillator (resolutions: 0.4 mm and 0.1 nsec in σ)
 - F3 chamber : PPAC, Plastic scintillator, and SSD (resolutions: 0.4 mm, 0.1 nsec, and 0.75% in σ)



KoBRA Beam Experiment : Plan

Projectile Fragmentation Reaction XS


^{40}Ar (25 MeV/u) + ^{12}C (0.1 mm)

Physics Model: EPAX 2.15

Z



Proton Pick-up →



Unit: mb

1.00E+03

1.00E+00

1.00E-03

1.00E-06

1.00E-09

Stable Nuclei

KoBRA Beam Experiment : Plan

^{32}Mg Yield Calculation

$$I = I_p \times \sigma_{Mg} \times \frac{\rho_A}{M} \times A_V \times \varepsilon_t \times \Omega_c$$

I_p = Intensity of primary beam ^{40}Ar = 100 pA

σ_{Mg} = ^{32}Mg XS calculated with EPAX 2.15 = 6.96E-04 mbarns

ρ_A = Area density of C target = 0.02253 g/cm²


M = Atomic mass of C target = 12.01 g/mol

A_V = Avogadro number = 6.022E+23 atoms/mol


ε_t = Transmission efficiency of ^{32}Mg to KoBRA F3
= 27.6% (1st order, MC cal.), 26.3% (5th order, MC cal.)

Ω_c = Correction factor for solid angle

Z vs A/q Distribution



^{32}Mg Transmission Efficiency (5th order MC)



DGKIM from KoBRA team

Transmission Efficiency
26.3% at F3 target

^{32}Mg (transported to F3)


Items	Yield	Solid angle correction
5 th order, LISE++	130 pps	150 pps

※ pps: particles per second

Proposed experiments with stable beams

- Study on neutron-deficient nuclei using proton-induced fusion-evaporation
- 3n fusion-evaporation reactions to study MEDs in $T_z = -3/2$ nuclei
- Fusion Reaction Studies related to Stellar Evolution
- The study of lifetime of isotopes near doubly magic $N=Z$ nuclei ^{40}Ca
- Optical model potential studies using stable beams at KoBRA
- Decay spectroscopy and fast-timing measurements by using KHALA at RAON
- High-resolution in-beam γ -ray experiments
- Internal conversion electron spectroscopy
- Spectroscopy of proton, neutron and alpha emitters
- RI experiments probing isospin symmetry
- Measurement of RI production cross section

Proposed by CENS/IBS




Cyclotron

◆ Specs

: 35~70 MeV proton, 0.75mA max with two beam lines connected to ISOL TIS bunker(Target Ion Source)

◆ Schedule



: Contract('19.6), pre-survey('19.11), Design finalized('20.4) ,
FAT ('21.6), Shipping('21.8), Installation('21.11.11~22.4.28)




SAT on Oct 2022



ISOL System





- Driver beam : proton 35<K<70 MeV, up to 70 kW
- Target : UCx, MgO, BN, CaO, BeO, **SiC**, etc
- Ion Source : **Surface**, **RILIS**, Plasma
- RIB : 6< A < 250, 10<K< 80 keV, 10⁸ pps(Sn), >90% purity @Exp.
- incident to RFQ of Post accelerator 10 keV/u
- full remote maintenance system with TIS modularization






- ISOL beam lines including sub-systems are commissioned with Cs beam in 2021
- RI beam commissioning using SiC target (Dec 2022)


ISOL Beam Test in 2021



Cs sample preparation in TIS chamber




F1 beam viewer



Beam emittance of TIS extracted Cs beam




$X(2\sigma) : 15 \text{ pi mm mrad}$

$Y(2\sigma) : 17 \text{ pi mm mrad}$




Beam size measurement by using F2 slit

ISOL Beam Test in 2021 (II)



Cs Total Number	Cs ²⁷⁺ Number (A/q=4.92)
1.50E+8	3.41E+7 (22.67%)

A/q spectrum and the present resolving power



Momentum dispersion of the A/q magnet: 1.244 m

Beam size in $2\sigma \sim \pm 5$ mm (from the slit width dependence of beam current)

→ Resolving power ~ 250 (2σ)

Our tuning is not finalized.

We may be able to obtain much higher resolving power (~ 400 in (2σ)) with careful tuning.

ISOL RI Beam Plan


❖ RI commissioning

- '22. 10 : Cyclotron SAT
- '22. 11 : RI Commissioning with SiC target & TIS module ISOL relocation/ operational parameter check with SI beam/proton beam
- '22.12~ : proton beam on SiC inside TIS module and Na^{20~25} extraction experiment
- ~'23.12 : Na & Al beam operation and experiments in ISOL hall

❖ RI Beam Schedule(~'24)

- non-fissile targets : SiC, BN, LaC₂, MgO
- Expected RI beams with 1 kW proton / at ISOL experimental hall
 - ²²Na(SIS) : 10^{6~7} pps / ²⁶Al(SIS+RILIS) : 10^{4~5} pps / ⁸Li(SIS) : 10^{6~7} pps
 - ^{131~132}Cs, ¹³¹Ba, ¹³⁵Ce

Other Experimental Systems



All exp. systems are to be installed and machine-commissioned by 2022.

SCL3 to KoBRA Beam Commissioning

❖ SCL3 → KoBRA SIB Commissioning ('22.10~'23.4)

- Ar(9+), $A/q = 4.44$, 100 μsec , 1 Hz, 30euA
 - SCL3 Linac SIB commissioning(~23.03)
 - SCL3-KoBRA beam transportation line(~23.4)
 - SCL3→KoBRA Secondary RI beam production experiment(23.4~) :
- Note>Ar beam specification/requirements on KoBRA target needs to discuss

SCL3 A/q Machine Study

❖ SCL3 A/q Machine Study using SIB('23.4~'23.6)

- Ar6+(6.67)/Ar7+(5.71)/Ar8+(4.0), ~70 euA('23.4)
- O5+(3.20)/O6+(2.67) with 30euA('23.5)
- Other gas beams(e.x. Ne)(23.6)
- ECR-IS extraction study : Ne6+, Kr14+, C4+, p & d, metal beam(Mg, Ca, Mo, Ag, Sn, Sm, Au)(~'24)

Note> Post acceleration of ISOL RI Beam: expect low beam current and need the same A/q of SIB for beam parameters such as pulse duration and repetition, timing

ISOL Beam Commissioning


❖ ISOL RIB Beam Commissioning

- Na-21 RIB commissioning using SiC target(22.12~23.3)
- Na-21/Al-26m using SiC to MMS/CLS(~23.12)
- LaC2 target for UC2 target preparation(~24)
- Low power(<1kW) UCx (~25)

Plan for '22~'24

❖ User beam experiments will open in '24. Q4

- RIBs from ISOL to be injected into SCL3 on 2023
- SIB experiments(ECR→SCL3 → KoBRA/NDPS) will be carried out in Q4 of 2023
- RIB experiments in ISOL beamline using AI isotope beams in 2023
- Call for the proposal in '23



Summary

❖ RAON is preparing for beam commissioning

- 1st beam extraction using 5 QWR CMs in SCL3 is successfully done.
- ECR → SCL3 → KoBRA using Ar-40(8+/9+) on Q2 of 2023
- Cyclotron → ISOL for RI beam extraction will be on Dec 2022

❖ Plan for ISOL → SCL3


- RIBs from ISOL to be injected into SCL3 on 2023

❖ Plan for SIB/RIB experiments

- SIB experiments(ECR→SCL3 → KoBRA/NDPS) will be carried out in Q4 of 2023
- RIB experiments in ISOL beamline using Al isotope beams

❖ Plan for “Call for Proposals in 2023”

Domestic Collaboration



User Groups and Collaborating Institution

1그룹 KOBRA	2그룹 LAMPS	3그룹 MMS	4그룹 CLS	5그룹 μSR	6그룹 NDPS	7그룹 BIS	8그룹 Theory